

ARKANSAS DEPARTMENT OF TRANSPORTATION



SUBSURFACE INVESTIGATION

STATE JOB NO. 090430

FEDERAL AID PROJECT NO. NHPP-0044(15)

PIGEON CREEK STR. & APPRS. (S)

STATE HIGHWAY 74 SECTION 3

IN MADISON COUNTY

The information contained herein was obtained by the Department for design and estimating purposes only. It is being furnished with the express understanding that said information does not constitute a part of the Proposal or Contract and represents only the best knowledge of the Department as to the location, character and depth of the materials encountered. The information is only included and made available so that bidders may have access to subsurface information obtained by the Department and is not intended to be a substitute for personal investigation, interpretation and judgment of the bidder. The bidder should be cognizant of the possibility that conditions affecting the cost and/or quantities of work to be performed may differ from those indicated herein.



ARKANSAS DEPARTMENT OF TRANSPORTATION

AR DOT.gov | IDriveArkansas.com | Scott E. Bennett, P.E., Director

MATERIALS DIVISION

11301 West Baseline Road | P.O. Box 2261 | Little Rock, AR 72203-2261 | Phone: 501.569.2185 | Fax: 501.569.2368

June 19, 2018

TO: Mr. Trinity Smith, Engineer of Roadway Design

SUBJECT: Job No. 090430
Pigeon Creek Str. & Apprs. (S)
Route 74 Section 3
Madison County

Transmitted herewith is the requested Soil Survey, strength data and Resilient Modulus test results for the above referenced job. The project consists of replacing the bridge crossing Pigeon Creek on Highway 74. Samples were taken in the existing travel lanes and ditch line. The shoulders are not paved within the project limits.

Based on laboratory results of samples obtained, the subgrade soils consist primarily of moderately plastic cherty clay. Cross-sections are not currently available, but it is assumed the construction grade line will closely match that of the existing roadway. The subgrade soils are expected to provide a stable working platform with conventional processing if the weather is favorable during construction. Rock was encountered at station 40+00 at 6 and 18 feet right of centerline at a depth of 3.0 feet.

There were no slide areas observed within the project limits. Earthwork recommendations will be made upon requests when plans are further developed and cross-sections are available.

Listed below is the additional information requested for use in developing the plans:

- 1. The Qualified Products List (QPL) indicates that Aggregate Base Course (Class CL-7) is available from commercial producers located in the vicinity of Farmington.
2. Asphalt Concrete Hot Mix

Table with 3 columns: Type, Asphalt Cement %, Mineral Aggregate %. Rows include Surface Course, Binder Course, and Base Course.

Handwritten signature of Michael C. Benson, Materials Engineer

MCB:pt:bjj
Attachment

cc: State Constr. Eng. - Master File Copy
District 9 Engineer
System Information and Research Div.
G. C. File

ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT - LITTLE ROCK, ARKANSAS
MATERIALS DIVISION
MICHAEL BENSON, MATERIALS ENGINEER
*** SOIL SURVEY STRENGTH TEST REPORT ***

DATE - 06/12/2018
JOB NUMBER - 090430

SEQUENCE NO. - 1
MATERIAL CODE - SSRV
SPEC. YEAR - 2014
SUPPLIER ID. - 1
COUNTY/STATE - 44
DISTRICT NO. - 09

JOB NAME - PIGEON CREEK STR. & APPRS. (S)

* STATION LIMITS R-VALUE AT 240 psi *

BEGIN JOB - END JOB 9

RESILIENT MODULUS
STA. 47+00 7271

REMARKS -

AASHTO TESTS : T190

**ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
MATERIALS DIVISION**

**AASHTO T 307-99 - RESILIENT MODULUS OF SUBGRADE SOILS
RECOMPACTED SAMPLES**

Job No.	090430	Material Code	SSRVPS
Date Sampled:	4/23/18	Station No.:	47+00
Date Tested:	May 15, 2018	Location:	18'LT
Name of Project:	PIGEON CREEK STR. & APPRS. (S)		
County:	Code: 44	Name: MADISON	
Sampled By:	THORNTON/BATES	Depth:	0-5
Lab No.:	20180679	AASHTO Class:	A-4 (1)
Sample ID:	RV 170	Material Type (1 or 2):	2
LATITUDE:		LONGITUDE:	

1. Testing Information:

Preconditioning - Permanent Strain > 5% (Y=Yes or N= No)	N
Testing - Permanent Strain > 5% (Y=Yes or N=No)	N
Number of Load Sequences Completed (0-15)	15

2. Specimen Information:

Specimen Diameter (in):	
Top	3.95
Middle	3.95
Bottom	3.95
Average	3.95
Membrane Thickness (in):	0.01
Height of Specimen, Cap and Base (in):	8.02
Height of Cap and Base (in):	0.00
Initial Length, Lo (in):	8.02
Initial Area, Ao (sq. in):	12.18
Initial Volume, AoLo (cu. in):	97.68

3. Soil Specimen Weight:

Weight of Wet Soil Used (g):	3320.60
------------------------------	---------

4. Soil Properties:

Optimum Moisture Content (%):	12.6
Maximum Dry Density (pcf):	117.5
95% of MDD (pcf):	111.6
In-Situ Moisture Content (%):	N/A

5. Specimen Properties:

Wet Weight (g):	3320.60
Compaction Moisture content (%):	12.9
Compaction Wet Density (pcf):	129.52
Compaction Dry Density (pcf):	114.73
Moisture Content After Mr Test (%):	12.9

6. Quick Shear Test (Y=Yes, N=No, N/A=Not Applicable):

#VALUE!

7. Resilient Modulus, Mr:

7495(Sc)^{-0.15366}(S3)^{0.40190}

8. Comments

9. Tested By:

GW

Date: May 15, 2018

**ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
MATERIALS DIVISION**

**AASHTO T 307-99 - RESILIENT MODULUS OF SUBGRADE SOILS
RECOMPACTED SAMPLES**

Job No. 090430 **Material Code** SSRVPS
Date Sampled: 4/23/18 **Station No.:** 47+00
Date Tested: May 15, 2018 **Location:** 18'LT
Name of Project: PIGEON CREEK STR. & APPRS. (S)
County: Code: 44 **Name:** MADISON
Sampled By: THORNTON/BATES **Depth:** 0-5
Lab No.: 20180679 **AASHTO Class:** A-4 (1)
Sample ID: RV 170 **Material Type (1 or 2):** 2
LATITUDE: **LONGITUDE:**

PARAMETER	Chamber Confining Pressure	Nominal Maximum Axial Stress	Actual Applied Max. Axial Load	Actual Applied Cyclic Load	Actual Applied Contact Load	Actual Applied Max. Axial Stress	Actual Applied Cyclic Stress	Actual Applied Contact Stress	Average Recov Def. LVDT 1 and 2	Resilient Strain	Resilient Modulus
	S ₃ psi	S _{cyclic} psi	P _{max} lbs	P _{cyclic} lbs	P _{contact} lbs	S _{max} psi	S _{cyclic} psi	S _{contact} psi	H _{avg} in	ε _r in/in	M _r psi
Sequence 1	6.0	2.0	25.2	22.3	2.8	2.1	1.8	0.2	0.00104	0.00013	14,098
Sequence 2	6.0	4.0	47.4	44.6	2.8	3.9	3.7	0.2	0.00220	0.00027	13,315
Sequence 3	6.0	6.0	70.1	66.5	3.6	5.8	5.5	0.3	0.00351	0.00044	12,467
Sequence 4	6.0	8.0	93.8	87.8	6.1	7.7	7.2	0.5	0.00511	0.00064	11,315
Sequence 5	6.0	10.0	117.7	109.1	8.5	9.7	9.0	0.7	0.00681	0.00085	10,561
Sequence 6	4.0	2.0	25.0	22.2	2.8	2.1	1.8	0.2	0.00126	0.00016	11,610
Sequence 7	4.0	4.0	46.8	44.0	2.8	3.8	3.6	0.2	0.00271	0.00034	10,668
Sequence 8	4.0	6.0	68.2	65.4	2.8	5.6	5.4	0.2	0.00434	0.00054	9,913
Sequence 9	4.0	8.0	91.7	86.6	5.2	7.5	7.1	0.4	0.00602	0.00075	9,463
Sequence 10	4.0	10.0	115.3	107.7	7.6	9.5	8.8	0.6	0.00777	0.00097	9,133
Sequence 11	2.0	2.0	24.7	21.9	2.8	2.0	1.8	0.2	0.00163	0.00020	8,831
Sequence 12	2.0	4.0	46.0	43.2	2.8	3.8	3.5	0.2	0.00344	0.00043	8,278
Sequence 13	2.0	6.0	66.6	63.8	2.9	5.5	5.2	0.2	0.00540	0.00067	7,778
Sequence 14	2.0	8.0	88.5	84.2	4.3	7.3	6.9	0.4	0.00745	0.00093	7,442
Sequence 15	2.0	10.0	111.6	104.8	6.8	9.2	8.6	0.6	0.00949	0.00118	7,271

TESTED BY _____ DATE May 15, 2018
 REVIEWED BY _____ DATE _____
 GW _____

**ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
MATERIALS DIVISION**

**AASHTO T 307-99 - RESILIENT MODULUS OF SUBGRADE SOILS
RECOMPACTED / THINWALL TUBE SAMPLES**

Job No.	090430	Material Code	SSRVPS
Date Sampled:	4/23/18	Station No.:	47+00
Date Tested:	May 15, 2018	Location:	18'LT
Name of Project:	PIGEON CREEK STR. & APPRS. (S)		
County:	Code: 44	Name:	MADISON
Sampled By:	THORNTON/BATES		
Lab No.:	20180679	Depth:	0-5
Sample ID:	RV 170	AASHTO Class:	A-4 (1)
LATITUDE:		Material Type (1 or 2):	2
		LONGITUDE:	


$$M_R = K_1 (S_C)^{K_2} (S_3)^{K_5}$$

$$K_1 = \underline{7,495}$$

$$K_2 = \underline{-0.15366}$$

$$K_5 = \underline{0.40190}$$

$$R^2 = \underline{0.98}$$



JOB: 090430

Arkansas State Highway Transportation Department

JOB NAME: PIGEON CREEK STR. & APPRS. (S)

Materials Division

COUNTY NO. 44 DATE TESTED 5/8/2018

Michael Benson, Materials Engineer

STA.#	LOC.	DEPTH	COLOR						L.L.	P.I.	SOIL CLASS	LAB #:	%MOISTURE
				#4	#10	#40	#80	#200					
				S	I	E	V	E	S				
47+00	18 LT	0-5	BROWN	88	82	76	69	57	25	06	A-4(1)	RV170	
40+00	06 RT	0-3Z	BR/GR	83	77	72	63	50	21	07	A-4(5)	S166	40.3
40+00	18 RT	0-3Z	BR/GR	97	78	65	59	52	36	20	A-6(7)	S167	34.7
47+00	06 LT	0-5	BR/GR	92	84	73	67	62	41	22	A-7-6(11)	S168	20.4
47+00	18 LT	0-5	BROWN	89	82	76	73	69	41	23	A-7-6(14)	S169	18.7

comments: W=MULTIPLE LAYERS

Friday, June 15, 2018

JOB: 090430

JOB NAME: PIGEON CREEK STR. & APPRS. (S)

Arkansas State Highway Transportation Department

Materials Division

DATE TESTED

5/8/2018

COUNTY NO. 44

Michael Benson, Materials Engineer

STA.# LOC.

PAVEMENT SOUNDINGS

40+00	06 RT	BST	ACHMSC	ACHMBC	AGG. BASE CRS CL-7
		4.0	---	1.5	7.0
40+00	18 RT	BST	ACHMSC	ACHMBC	AGG. BASE CRS CL-7
		---	---	---	---
47+00	06 LT	BST	ACHMSC	ACHMBC	AGG. BASE CRS CL-7
		2.0	4.0	1.5	5.0
47+00	18 LT	BST	ACHMSC	ACHMBC	AGG. BASE CRS CL-7
		---	---	---	---

comments: W=MULTIPLE LAYERS

