

ARKANSAS DEPARTMENT OF TRANSPORTATION

A00070

HWY. 62 – MISSOURI STATE LINE (S)

FEDERAL AID PROJECT STPR-0011(67)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND OVERLAY APPROXIMATELY 4.860 MILES OF HIGHWAY 1 IN CLAY COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 1

SECTIONS: 22

COUNTY: CLAY

LENGTH: 4.86 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	60.00	LF
215011	TRENCH.AND SHOULDER PREP.	257.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	770.00	TON
401011	TACK COAT	15,087.00	GAL
406161	M.A. IN ACHM BINDER(1")	2,594.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	122.00	TON
407162	MA IN ACHM SURFACE(1/2")	10,753.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	638.00	TON
412002	COLD MILLING ASPHALT PVMT.	542.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	25.00	TON
504264	APPROACH GUTTERS	21.16	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	301.00	SQFT
604041	CONST.PAVEMENT MARKINGS	102,645.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	530.00	LF
604083	VERTICAL PANELS	10.00	EACH
617005	GUARDRAIL (TYPE A)	225.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	2.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	2.00	EACH
637001	MAILBOXES	9.00	EACH
637011	MAILBOX SUPPORTS (SINGLE)	9.00	EACH
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	41,057.00	LF
718002	REFL.PAINT PVMT.MRK.WH(6")	51,325.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	51,325.00	LF
721002	RAISED PAVEMENT MARKERS-2	325.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	2,460.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 2.0%.