

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30033

HWY. 371 – HWY. 29 (S)

FEDERAL AID PROJECT STPR-0050(37)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 8.445 MILES OF HIGHWAY 19 IN NEVADA COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 19

SECTIONS: 5

COUNTY: NEVADA

LENGTH: 8.445 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202052	R&D OF APPROACH GUTTERS	12.00	EACH
202132	R&D OF GUARDRAIL	1,950.00	LF
303117	AGGR.BASE COURSE(CLASS 7)	1,615.00	TON
401011	TACK COAT	39,650.00	GAL
407162	MA IN ACHM SURFACE(1/2")	24,366.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	1,473.00	TON
412002	COLD MILLING ASPHALT PVMT.	179,738.00	SQYD
504264	APPROACH GUTTERS	68.28	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	708.00	SQFT
604041	CONST.PAVEMENT MARKINGS	183,349.00	LF
617005	GUARDRAIL (TYPE A)	1,950.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	8.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	12.00	EACH
620001	LIME	3.00	TON
620011	SEEDING	1.43	ACRE
620022	MULCH COVER	4.29	ACRE
620030	WATER	204.20	MGAL
621001	TEMPORARY SEEDING	2.86	ACRE
621021	SILT FENCE	3,200.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	119.00	CUYD
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	43,681.00	LF
718002	REFL.PAINT PVMT.MRK.WH(6")	20,244.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	20,244.00	LF
719002	THERMO.PVMT.MARK.WH(6")	68,936.00	LF
719102	THERMO.PVMT.MARK.YL(6")	73,925.00	LF
721002	RAISED PAVEMENT MARKERS-2	1,889.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	7,860.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 5.0%.