

ARKANSAS DEPARTMENT OF TRANSPORTATION

A40031

FAYETTEVILLE – BENTON CO. LINE (S)

FEDERAL AID PROJECT STPF-0072(74)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND OVERLAY APPROXIMATELY 7.133 MILES OF HIGHWAY 112 IN WASHINGTON COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 112

SECTIONS: 1

COUNTY: WASHINGTON

LENGTH: 7.133 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	1,088.00	TON
401011	TACK COAT	18,405.00	GAL
407161	MA IN ACHM SURFACE(3/8")	9,704.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	664.00	TON
412002	COLD MILLING ASPHALT PVMT.	8,210.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	150.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	380.00	SQFT
604041	CONST.PAVEMENT MARKINGS	154,582.00	LF
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	728.00	LF
718004	REFL.PAINT PVMT.MRK.WH(10")	138.00	LF
719002	THERMO.PVMT.MARK.WH(6")	76,138.00	LF
719005	THERMO.PVMT.MARK.WH(12")	72.00	LF
719102	THERMO.PVMT.MARK.YL(6")	78,444.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	8.00	EACH
721002	RAISED PAVEMENT MARKERS-2	967.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 7.0%.