

ARKANSAS DEPARTMENT OF TRANSPORTATION

A50031

HWY. 9 – INDEPENDENCE CO. LINE (S)

FEDERAL AID PROJECT STPR-0069(24)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND PLACE ULTRATHIN BONDED WEARING COURSE WITH 2' SHOULDERS ON APPROXIMATELY 21.977 MILES OF HIGHWAY 14 IN STONE COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, FOG SEAL, ACHM BINDER AND SURFACE COURSES, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 14

SECTIONS: 7

COUNTY: STONE

LENGTH: 21.977 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202052	R&D OF APPROACH GUTTERS	23.00	EACH
202132	R&D OF GUARDRAIL	4,994.00	LF
210213	UNCLASSIFIED EXCAVATION	550.00	CUYD
210611	COMPACTED EMBANKMENT	550.00	CUYD
215011	TRENCH.AND SHOULDER PREP.	836.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	5,285.00	TON
401007	FOG SEAL (TYPE 4)	2,327.00	GAL
401011	TACK COAT	8,795.00	GAL
406161	M.A. IN ACHM BINDER(1")	6,335.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	298.00	TON
407162	MA IN ACHM SURFACE(1/2")	8,138.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	510.00	TON
407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	13,780.00	TON
412002	COLD MILLING ASPHALT PVMT.	2,341.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
504264	APPROACH GUTTERS	166.27	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,585.00	SQFT
604041	CONST.PAVEMENT MARKINGS	476,207.00	LF
617005	GUARDRAIL (TYPE A)	3,400.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	17.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	11.00	EACH
620001	LIME	2.00	TON
620011	SEEDING	1.00	ACRE
620022	MULCH COVER	1.00	ACRE
620030	WATER	102.00	MGAL
621021	SILT FENCE	1,000.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	50.00	CUYD
621168	FILTER SOCK (12")	1,000.00	LF
623001	SECOND SEEDING APPLICATION	1.00	ACRE
637001	MAILBOXES	60.00	EACH
637011	MAILBOX SUPPORTS (SINGLE)	30.00	EACH

637012	MAILBOX SUPPORTS (DOUBLE)	15.00	EACH
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	209,246.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	16,980.00	LF
719002	THERMO.PVMT.MARK.WH(6")	238,869.00	LF
719005	THERMO.PVMT.MARK.WH(12")	78.00	LF
719102	THERMO.PVMT.MARK.YL(6")	237,339.00	LF
719201	THERMO.PVMT.MARK.(WORD)	3.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,837.00	EACH
734011	BRIDGE END TERMINAL	15.00	EACH
804013	REINF.STEEL-BRIDGE (GR 60)	16,307.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 6.0%.