

ARKANSAS DEPARTMENT OF TRANSPORTATION

A60047

MISSISSIPPI AVE. – S. CROSS ST. (SEL. SECS.) (LITTLE ROCK) (S)

FEDERAL AID PROJECT NHPP-0060(78)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 4.070 MILES OF HIGHWAY 10 IN PULASKI COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 10

SECTIONS: 8

COUNTY: PULASKI

LENGTH: 4.07 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	21,624.00	GAL
407162	MA IN ACHM SURFACE(1/2")	13,208.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	14.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	770.00	TON
412002	COLD MILLING ASPHALT PVMT.	114,672.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	200.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,628.00	SQFT
604041	CONST.PAVEMENT MARKINGS	124,432.00	LF
719002	THERMO.PVMT.MARK.WH(6")	11,951.00	LF
719003	THERMO.PVMT.MARK.WH(8")	950.00	LF
719005	THERMO.PVMT.MARK.WH(12")	1,388.00	LF
719102	THERMO.PVMT.MARK.YL(6")	50,265.00	LF
719201	THERMO.PVMT.MARK.(WORD)	13.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	11.00	EACH
721002	RAISED PAVEMENT MARKERS-2	789.00	EACH
901224	JOINT TAPE (24")	10,890.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 2.0%.