

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70017

CADDO VALLEY – HOT SPRING CO. LINE (SEL. SECS.) (S)

FEDERAL AID PROJECT STPR-0010(55)

THE PURPOSE OF THIS PROJECT IS TO APPLY AN ULTRATHIN BONDED WEARING COURSE TO APPROXIMATELY 3.367 MILES OF HIGHWAY 7 IN CLARK COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 7

SECTIONS: 7

COUNTY: CLARK

LENGTH: 3.367 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	5,421.00	GAL
407162	MA IN ACHM SURFACE(1/2")	300.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	19.00	TON
407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	3,562.00	TON
412002	COLD MILLING ASPHALT PVMT.	978.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	85.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	393.00	SQFT
604041	CONST.PAVEMENT MARKINGS	76,612.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	2.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	3.00	EACH
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	28,444.00	LF
719002	THERMO.PVMT.MARK.WH(6")	36,547.00	LF
719102	THERMO.PVMT.MARK.YL(6")	40,065.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	3.00	EACH
721002	RAISED PAVEMENT MARKERS-2	315.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 22, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 5.0%.