

ARKANSAS DEPARTMENT OF TRANSPORTATION

A80035

YELL CO. LINE – PERRY (S)

FEDERAL AID PROJECT STPR-0053(40)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 18.227 MILES OF HIGHWAY 10 IN PERRY COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, AGGREGATE BASE AND SURFACE COURSES, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 10

SECTIONS: 5

COUNTY: PERRY

LENGTH: 18.227 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	520.00	LF
303117	AGGR.BASE COURSE(CLASS 7)	50.00	TON
303308	AGGREGATE SURFACE COURSE (CLASS D-8)	555.00	TON
401011	TACK COAT	59,324.00	GAL
407162	MA IN ACHM SURFACE(1/2")	35,451.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	2,343.00	TON
412002	COLD MILLING ASPHALT PVMT.	343,579.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	458.00	TON
415011	ACHM PATCH.EXIST.RDWY.	740.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,882.00	SQFT
604041	CONST.PAVEMENT MARKINGS	649,712.00	LF
617005	GUARDRAIL (TYPE A)	425.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	5.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	5.00	EACH
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	68,038.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	85,047.00	LF
719002	THERMO.PVMT.MARK.WH(6")	192,814.00	LF
719005	THERMO.PVMT.MARK.WH(12")	36.00	LF
719102	THERMO.PVMT.MARK.YL(6")	132,042.00	LF
719201	THERMO.PVMT.MARK.(WORD)	1.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	1.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,212.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE December 13, 2024.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 5.0%.