

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0146

HWY. 152 – SOUTH (LEVELING & RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND RESEAL APPROXIMATELY 3.20 MILES OF COUNTY ROAD 3 IN ARKANSAS COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: CR 3

COUNTY: ARKANSAS

LENGTH: 3.20 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	600.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	624.00	TON
402204	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	14,268.00	GAL
407161	MA IN ACHM SURFACE(3/8")	374.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	26.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	148.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	47,520.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 11, 2024.